BRAHMAPUTRA VALLEY FERTILIZER CORPORATION LIMITED

(A GOVT OF INDIA UNDERTAKING) P.O – Parbatpur (786,623) Dist – Dibrugarh, Assam

ELECTRICAL DEPARTMENT NOTICE INVITING TENDER

Annexure-I

Tender notice no- Nam/Elect-TSM/NIT-02/2017/259

Date: 10/02/2017 Sealed tenders are hereby invited in single bid system on item rate/ Lump sum basis from experienced contractors for the following work(s) in Brahmaputra valley Fertilizer Corporation Limited, Namrup.

SI	Name of the work	Earnest	Completion	Tender
No		Money (Rs)	time: days/	paper
		, ,	Months	cost (Rs)
01	02	03	04	05
	"Electrification job required for shifting of			
01	Biofertilizer Plant inside Factory."	10, 600.00	45 days	100.00
	Estimated amount: Rs. 4, 23,461.00 incl. of taxes.			

Contractor means the experienced, licensed contractors who are having past experience for respective Electrical jobs; and:

- a) Contractors having up to date renewed Electrical License/ Electrical supervisors certificate of Competency, issued by Electrical Licensing Board, Government of Assam, holding supervisors under their employment. The Electrical supervisor's certificate of Competency holder should be associated with the Contractor / firm and should be duly endorsed by the Electrical Licensing Board.
- b) Party having registration fulfilling the conditions of statutory levies like VAT, Service Tax etc. as admissible.
- c) Party should submit photocopy of PAN, and all relevant documents mentioned at Sl. No: a) & b).
- d) Party shall have to produce all documents, as mentioned above, in original if asked for.
- e) Party should submit experience of having successfully completed similar works during last 7 (seven) years ending last day of month previous to the one in which applications are invited should be either of the following:
- i) Three similar completed works costing not less than the amount equal to 40% of the estimated cost.

ii) Two similar completed works costing not less than the amount equal to 50% of the estimated cost.

iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost

- Party should fulfill all the above criteria from (a) to (d) as above.
- 01 Tender paper [NIT, schedule of quantities, special terms & conditions (Annexure-II & Annexure-iv) GDCC] are to be downloaded from the web site www.bvfcl.com. Tender paper cost and earnest money drawn in favour of BVFCL Namrup by DD/Banker cheque shall have to be submitted along with bid documents. OR Tender paper cost and earnest money may also be deposited in BVFCL Bank Account in SBI through Challan that can be downloaded through BVFCL website. One Challan copy must be submitted along with the tender documents. The DD / Bankers cheque against Tender paper cost and EMD shall be put in one envelope super scribed. The bid shall be put in one sealed envelope super scribed and both envelopes will be put on a third envelope properly super scribed & super scribed.
 - 1. Submission of Tender paper (To be put in locked tender paper box) in the office of the CE (Elect) BVFCL, Namrup

2. Last date of submission of tender papers : 23 - 02 - 2017 up to 3.00 PM

3. Opening date of Tender papers : 23 – 02 - 2017 at 3.30 PM

02. The tenders will be opened on the above scheduled date and time in presence of the tenderer or their authorized representatives who may like to be present. In case of Bandh or Holiday, next working day shall be considered for opening of tender and such will be informed to the expressing interest in taking part.

03. BVFCL shall not be responsible for late submission of tender.

Contd.

- 04. BVFCL reserves the right to accept or reject any or all tenders communicating same to the party (ies) without assigning any reason thereof.
- 05. Additional Terms: Every bidder will submit a declaration in the form of affidavit/ declaration that he/she is not a partner / proprietor of any other firm/ company participating in this tender of BVFCL.
- 06. **PAYMENT TERMS:** You will be paid for the work as.
 - a) 90% payment will be made to you on actual work carried out & successfully completed by you, duly certified by site Engineer.
 - b) Balance 10% will be released after completion of workmanship guarantee period. You will be paid no running bills for this job.

 At no time the progress of work shall be retarded or stopped due to the disr

At no time the progress of work shall be retarded or stopped due to the disputes or differences with BVFCL, Namrup.

- i. Income tax and other taxes if any shall be deducted from your bill as per rules as applicable. Security Deposit @ 10% of the total value of work done shall be recovered from your bill after the adjustment of Earnest Money Deposited by you for the said work, unless you furnish a Bank Guarantee in your approved proforma in lieu of the same.
- ii. Where supply of materials is involved, the list of material supplied by you are to be entered in the register in the site office under a valid challan along with the documentary proof for purchased materials are to be submitted along with the bill for necessary checks at our end.

07. **ARBITRATION**:-

- a) Any Disputes or differences whatsoever arising between the parties and/or relating to the construction, interpretation, application, meaning, scope, operation or effect of this contract or the validity or the breach thereof, shall be settled by arbitration in accordance with the "Rules Of Conciliation and Arbitration" by ICADR as decided by the Competent Authority of BVFCL. The award made in pursuance thereof shall be final binding on both the parties. Further all disputes arising out of this contract shall be subject to the jurisdiction of courts of Dibrugarh.
- 08 EMD of the unsuccessful bidders shall be returned back after finalization of the Contract.
- 09 Security Deposit and EMD would not bear any interest.
- 10 Considering the essence of the work, it may be required to execute the job in odd hours.
- 11 BVFCL is committed to a corruption free work environment. All the works/ purchases / services contracts and commitments of BVFCL will be honored without the citizen having to pay any bribe. In case any person demands any bribe, it is the duty of the responsible citizen to inform the matter to Vigilance Officer, BVFCL, Namrup PO Parbatpur, Dist Dibrugarh, Assam, Pin code- 786623.

(T J Gohain) P.E (Elect)

Copy To:-

1.0 Dy. FM: - to kindly depute his representative at the time of opening.

2.0 CE (E)-HOD

3.0 Sr. Vigilance Officer

BRAHMAPUTRA VALLEY FERTILIZER CORPORATION LIMITED (A GOVT OF INDIA UNDERTAKING) P.O – Parbatpur (786623) Dist – Dibrugarh, Assam ELECTRICAL DEPARTMENT SCHEDULE OF QUANTITIES

Date: 10/02/2017

Tender notice no- Nam/Elect-TSM/NIT-02/2017/259

SI No.	Description of Work	Qty		Rate (Rs.)	Amount (Rs)
1	Dismantling and shifting of cable from cable trench & cable rack of N-III from Instrument Air Compressor to CPP substation	1	Nos.		
2	Laying of PVC insulated PVC sheathed Aluminium 3.5 core power cable of 1.1KV grade of size 120 sq.mm. through underground from MM Department substation to the site.	135	Mtrs.		
3	Supply, laying & clamping of PVC insulated PVC sheathed 3 core power cable of 1.1KV grade of size 25 sq.mm. through the existing wall at Biofertilizer	210	Mtrs.		
4	Shifting of MCC panel from the departmental store and Installation of the same in the floor of the MCC room at Biofertilizer.	1	Unit		
5	Repairing of MCC panel for connection of Incoming & out going feeders	1	Unit		
6	Supply & Installation of 6 ways, 63A, TPN rewireable type distribution board on nearby wall to the main switch. This job includes connection of power supply to the DB with main switch and MCB.	1	Unit		
7	Supply & Installation of 63A TPN MCB on nearby wall to the machine. This job includes connection of power supply to the MCB with the cable and motor.	10	Nos.		
8	Making of earth pit after excavation, with G. I. pipe of 3 m long and 40 mm diameter providing RCC cover-plate in the ratio of 1:2:4 of size 0.53 m x 0.53 m x 0.05 m with reinforcement of 8 mm dia. rod to cover the pit. Brick work to be made with 6 inches above ground and 18 inches below the ground. Applying plain cement concrete in the ratio of 1:4:8 on the brick wall above the ground. Treating the soil with salt and charcoal to get the earth resistance to a maximum value of 1 (one) ohm. Providing necessary bolt to enable earth connection.	2	Nos.		
9	Supply and fixing of G.I. wire of 8 SWG for earthing of the Equipments as required.	150	Mtrs.		

SI No.	Description of Work	Qty		Rate (Rs.)	Amount (Rs)
10	Wiring for sub-main with 2×6 sq. mm. PVC insulated PVC sheathed Aluminium conductor cable in PVC pipe, PVC casing and capping including PVC bends etc as required.	30	Mtrs.		
11	Circuit wiring with 1×2.5 sq. mm. PVC insulated PVC sheathed Aluminium conductor cable in PVC pipe, PVC casing and capping including PVC bends etc as required.	180	Mtrs.		
12	Wiring for light & fan point with1×1.5 sq. mm PVC insulated PVC sheathed Aluminium conductor cable in PVC pipe, PVC casing and capping including PVC bends etc as required.				
	i) Short Point	20	Mtrs.		
40	ii) Medium Point	18	Mtrs.		
13	Supply and drawing of 18 mm2 Al-conductor bare Wire for loop earthing along with other wires for circuit wiring as required	170	Mtrs.		
14	Supplying and replacing of Bakelite board with thickness 2.5 to 3.5 mm coated with white sun mica of the following sizes:				
	a) 4" x 4"	66	Nos.		
	b) 6" x 8"	10	Nos.		
	c) 10" x 12"	9	Nos.		
15	Fixing of the following, making connections etc. as required including supply of the required materials of reputed make like Anchor / Ellora.				
	a) Piano type switch of 5 Amps capacity,	38	Nos.		
	b) Piano type 3 pin switch socket combined 5 Amps capacity	8	Nos.		
	c) 3 pin switch socket combined 15 Amps capacity	8	Nos.		
16	Supply and Fixing of Ceiling rose	42	Nos.		
17	Supply, installation, Testing & Commissioning of 6 way MCB Distribution Board	3	Nos.		
18	Supply & Installation of Ceiling fan regulator	14	Nos.		
19	Supply & Installation of 18 Watt LED Tube Light	24	Nos.		
20	Supply & Installation of Industrial type Plug & Socket board	4	Nos.		
21	Supply & Installation of Exhaust Fan	2	Nos.		
Total in Rs.					

Total Rupees.....only inclusive of taxes